


6th Meeting of the WEST Governing Board



OVERVIEW OF OPERATION FOR THE C3 CAMPAIGN



Jérôme BUCALOSSI, on behalf of the WEST team

Château de Cadarache – May 17, 2019

DE LA RECHERCHE À L'INDUSTRIE



www.cea.fr

WEST IN MAY 2018 MACHINE CONFIGURATION FOR C3 CAMPAIGN

New features for C3:
4 add. IL-PFUs (F4E)
2 ICRH antennas
Divertor Vis. spectro
IR VHR endoscope
GEM (soft X-rays)
X2D
ORNL collector probe
NIFS samples

The test sector with 12 ITER-like PFUS

EXPERIMENT TIMELINE FOR 2018 (END OF PHASE 1)

- **C3**: 11 weeks of plasma operations → 8 weeks of experiments (~32 days)
 - Objective 1: increase injected power **towards 5 MW (H-mode)**
 - Objective 2: first experiments on ITER-like PFU prototypes **towards 10 MW/m²**

Jan					Feb				Mar				Apr					May				Jun				Jul				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
C2						S2																	C3							

GB5

- **S3**: installation of IC3 (full heating capability), IR views (~full coverage)
- **C4**: 10 weeks of plasma operations → 7 weeks of experiments (~28 days)
 - Objectives: **He campaign**, long pulse operations (upper divertor)

Aug					Sep					Oct					Nov					Dec		
32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52		
S3										C4												


	Shutdown
	Commissioning
	Experiment

- **Contingency**: 11 weeks in 2019 (up to end of March 2019) → will depend on C3 and C4 results and PFU availability for phase 2

C2b+C3+C4 = 26 weeks of plasma operations in 2018

WEST GB5, 18 MAY 2018 | PAGE 2

LEAKS DURING INITIAL BAKING → C3 EXTENDED, C4 POSTPONED TO 2019



C2b+C3 = 20 weeks of plasma operations / 26* initially planned

	2018	C2b	C3a	C3b
Number of days with plasma (except maintenance, technical and boronization days)	74	19	20	35
Number of sessions	138	37	38	63
Early Shift : 8h-14h30 (6h30)	63	18	17	28
Late Shift : 14h30-21h (6h30)	66	19	18	29
Standard shift = Early Shift + Contingency + Commissioning	9	0	3	6


Contingency=14h30-16h15 (1h45) / Commissioning=16h15-18h30 (2h15)

Main achievements

- **5.5 MW of total injected power** achieved
- First EUROfusion Key Performance Indicator (KPI) achieved
 - KPI#1: “*H-mode, 2s*” → up to 5.5MW injected, $P_{\text{sep}} \leq P_{\text{LH}}$ (~2.5MW?)
 - KPI#2: “*1MW/m² for 1MW of input*” → 1MW/m² for 2MW of input (L-mode)
 - KPI#3: “*1MW of ICRF in H-mode*” → 1.4MW ICRH obtained in L-mode
 - KPI#4: “*30s flattop*” → **37s pulse achieved**
 - KPI#5: “*H-mode, 10s, 5MW/m²*” → L-mode, 10s, 2MW/m² achieved
- 21 EUROfusion sessions executed
- **~2h plasma exposure**


Issues

- High radiation level (50%), several boronizations performed
- MHD during current ramp-up due to central radiation (W)
- Disruptions in ramp-down




Test sector showing plasma footprint after C3

2018 EXPERIMENTAL CAMPAIGNS SESSIONS BREAKDOWN




~50% of the sessions dedicated to commissioning, ~25% to baseline scenario development and ~25% to experiments

- **Improvement of the R, Z control** when ramping up divertor currents and when switching from (R, Z) to (EROG, Z) control: adjustment of feedforward divertor currents
- **Improvement of the coupling** of the heating systems (EROG control)



Idiv ramp-up

(R,Z) $\rightarrow$ (EROG,Z) ctrl






Idiv ramp-up

(R,Z) $\rightarrow$ (EROG,Z) ctrl

VARIATION OF X-POINT POSITION


- Scan in X-point height in feedforward I_{div} : stable up to 12 cm
- Design of specific equilibrium: Strike Points on pre-damaged monoblocks




“Close” X-point ($dx \sim 3cm$)

“Far” X-point ($dx \sim 8cm$)

Strike point on pre-damaged monoblocks ($dx \sim 12cm$)




- Wall temperature limited to 120°C during C3 due to divertor casing leaks (resin outg.)
- **3 boronizations** performed (He+10% B₂H₆ glow discharge)
 - Reduction of the oxygen level on the RGA
 - Reliable plasma startup → **long lasting effect**
 - **Extension of the operational domain** (higher n_e) → **long lasting effect**
 - Reduction of the radiated power fraction → **short term effect (few pulses)**




Oxygen level from the residual gas analyser (RGA) after the 3 boronizations performed during C3

- For C4: 200°C baking and more frequent boronization


- The avalanche phase easily achieved (poorly affected by plasma facing materials)
→ burn-through phase hard to pass during C2
- The first boronization performed in C3 strongly ease the burn-through phase
- Low loop voltage ohmic startup (down to 0.4V/m) achieved after boronization



*Successful plasma
initiation conditions
before and after
boronization*




- Boronizations significantly reduce the occurrence of runaway electrons (RE)
- Anti-RE strategy implemented during C2 not 100% safe (startup conditions changed by the boronization)
- One RE beam impact on the baffle (#53378, 400kA)



- Real time protection on neutron production has been implemented for C4 (10ms above a threshold)


- Higher density achievable $\rightarrow n_l = 1.5 \cdot 10^{19} \text{m}^{-2}$ before boronization, $4 \cdot 10^{19} \text{m}^{-2}$ achieved



Radiated power normalized to the line integrated density as a function of the line integrated density

- Higher LH power and IC power achievable $\rightarrow 5.5 \text{MW}$ of LH and 1.4MW of IC achieved
- Reduced edge radiation $\rightarrow$ higher heat fluxes on the divertor targets, 2.5MW/m^2 achieved


- Hotter plasma edge leads to contaminated core plasma → **hollow temperature profile**
 - can prevent $q=1$ appearance or lead to off-axis sawteeth that do not clean the core
 - evidence of plasma cleaning by Double-Tearing Mode crash



5 consecutive discharges with the same setup and different MHD behaviours (white and magenta are successful!)

- Crucial role of (2,1) mode in the preforming
 - locked (2,1) not lethal but prevents successful LH application
 - (2,1) can be stabilized when approaching sawtooth regime
- ~33% of the pulses stopped due to MHD modes during C3** → plasma startup optimization/preforming studies planned during C4

- Disruption at the end of the heating phase or early in the current ramp-down
- No significant impact on the following pulse



- Ramp down sequence to be addressed during C4

	Nb Plasma	Nb sustained	I _p max (kA)	Duration max (s)	Cumul (s)	Disruptions	Disruptivity	LH (pulse)	LH max (MW)	W LH total (MJ)	IC (pulse)	IC max (MW)	W IC total (MJ)
C2a 2017	416	26%	425	2.96	58	45	79%	21	0.24	0.42	0	0	0
C2b	300	88%	805	10.52	1495	237	92%	147	2.47	95.1	0	0	0
C3a	357	84%	710	16.5	1244	181	72%	142	3.38	163.8	40	0.74	7.6
C3b	719	96%	818	37.51	6058	549	81%	430	5.34	4783	146	1.42	97
Thermal pulses!													
All	1792	76%	818	37.51	8855	1012	82%	740	5.34	5042	186	1.42	104.6

2h30* of plasma exposure, 5 GJ** of energy injected

*corresponding to ~9 WEST nominal pulses (1000s)

**corresponding to ~50% of one WEST nominal pulse (10MW, 1000s)



Commissariat à l'énergie atomique et aux énergies alternatives
 Centre de Cadarache | 13108 Saint Paul Lez Durance Cedex
 T. +33 (0)4 42 25 46 59 | F. +33 (0)4 42 25 64 21

Etablissement public à caractère industriel et commercial | RCS Paris B 775 685 019

DRF
 IRFM
 WEST