

6th Meeting of the WEST Governing Board



TIMELINE FOR THE C4 CAMPAIGN




Jérôme BUCALOSSI, on behalf of the WEST team

Château de Cadarache – May 17, 2019


DE LA RECHERCHE À L'INDUSTRIE




www.cea.fr

The background of the slide is split into two main sections. The left section features a series of concentric, hand-drawn circles in shades of blue, green, and purple, creating a ripple effect. The right section is a solid red gradient that transitions from a lighter shade at the top to a darker shade at the bottom. The text 'MACHINE CONFIGURATION FOR C4' is written in white, bold, uppercase letters on the red background.

MACHINE CONFIGURATION FOR C4





- 14 prototypes from all potential suppliers of ITER divertor VT installed
- 4 with sharp edges
- Alignment within ITER tolerances (4 with max tolerance 0.3mm)
- One groove on an outer monoblock for melting studies (PFU7)



Commissioning

IC2-Q1B

IC1-Q2B

IC3-Q4A

LH1-Q6A

LH2-Q6B



1MW CW
3MW 30s


1MW CW
3MW 30s

1MW CW
3MW 30s

4MW CW

3MW CW

NEW MASSIVE TUNGSTEN MOVABLE OUTBOARD LIMITER



IR system

- Full coverage of the 5 RF antennas
- 66% coverage of the lower divertor

Bolometry

- 8 vertical lines towards divertor baffle (upper Q5B)

ECE imaging

- Mirrors have been installed in the vacuum vessel
- **Air leak** on the window seal → repair ongoing (may not be available for C4)

CAES VUV spectroscope

- Ready for commissioning

Pellet injector



- All the tracks connected and operational: LFS mid plane, vertical, HFS mid plane, HFS lower X-point



Optical heads of the vertical IR endoscopes

A MAJOR INCIDENT ON A CRYOGENIC COMPRESSOR DELAYS C4 CAMPAIGN

- Last week, just before the start of the baking of the vessel, abnormal vibrations were recorded on the C4 compressor (4 compressors required for normal operation)
- **Compressor removed on May 10** and sent to Axima premises for failure analysis:
 - Ball bearing of main screw deeply damaged
 - “Half box” damaged with multiple rifts
 - Metallic chips spread in the compressor
- “Half box” not repairable → no spare available
- **Refurbished used compressor found** → available under a couple of weeks



Plasma restart for C4 can be expected for mid-July instead of mid-May as initially planned (in EUROfusion call for participation)



OBJECTIVES AND TIMELINE OF C4

- **10 MW of injected RF power** (~6 MW of LHCD / ~4 MW of ICRH)
→ H-mode operation (EUROfusion KPI)
- **He campaign**
→ He-W Plasma-wall interactions studies (EUROfusion experiments)
- **1 minute long pulses** (upper divertor)
→ Plasma scenario for high fluence campaigns (phase 2)

TENTATIVE TIMELINE FOR 2019

- Assuming compressor replacement in 6 weeks
- 13 weeks for C4 campaign** → ~60 experimental sessions
- End mid-October for phase 2 shutdown

2019																																	
May				Jun				Jul				Aug				Sep				Oct				Nov				Dec					
19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52
									D2	D2	D2	D2	D2			D2	EF D2	EF D2	D2	EF He	EF He	EF He	He										
S3								C4																S4									

- Backup solution** in case of delays for the compressor replacement
- 13 weeks for C4 campaign** → ~60 experimental sessions
- Shift of C5 campaign (Phase 2) in Sept 2020

	Vessel venting		
	Plasma commissioning		
	D2 experiment		
	He experiment		

2019																																	
May				Jun				Jul				Aug				Sep				Oct				Nov				Dec					
19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52
																			D2	D2	D2	D2	D2	D2	EF D2	EF D2	D2	EF He	EF He	EF He	He		
S3												To be consolidated soon!												C4								S4	

To be consolidated soon!

Wk	Main TF	Gas	Main experiment	Objective
1	C	D2	Ohmic / LH+IC vacuum cond.	40kA pre-magnetization
2	C	D2	LH + IC ramp up	2.5MW LH, 1 MW IC / 2T Ohm
3	C	D2	LH + IC ramp up	5MW LH, 1.5 MW IC / 2T Ohm
4	W2	D2	High Conf. 3.7T	4 MW IC (+LH)
5	W2	D2	High Conf. 3.7T	6 MW LH + 4 MW IC
6	W2	D2	High Fluence. 3.7T / 2T	6 MW LH + 4 MW IC / 6 LH
7	W1	D2	Lq (1) / LPO N2 (1)	EUROfusion D2 expt
8	W1	D2	Pre-damaged (5)	EUROfusion D2 expt
9	W	D2	Contingency	Contingency
10	W1	He	Changeover (3) / Sources (2)	EUROfusion He expt
11	W1	He	Lq (3) / Sources (2)	EUROfusion He expt
12	W1	He	He PWI (5)	EUROfusion He expt
13	W	He	Contingency	Contingency

If H-mode not reached @ 3.7T



W1 in addition to EUROfusion sessions (22)

- W source: divertor vs main chamber (1 session)
- Divertor regimes (1 session in D2 and 1 session in He)
- “High Heat Flux” scenario development (2 session)
- Shaping / tolerance to PFU misalignement (3 sessions)
- PFU melting experiments (2 session)

W2 in addition to scenario development sessions (15)

- Ohmic and L mode confinement (1 session)
- L-H power threshold (1 session)
- ELM regime (1 session)
- H mode confinement (1 session)
- I mode access on USN at 3.7T (1 session)

~10 contingency sessions



Commissariat à l'énergie atomique et aux énergies alternatives
 Centre de Cadarache | 13108 Saint Paul Lez Durance Cedex
 T. +33 (0)4 42 25 46 59 | F. +33 (0)4 42 25 64 21

Etablissement public à caractère industriel et commercial | RCS Paris B 775 685 019

DRF
 IRFM
 WEST